



Contact Officer: Wayne Prangnell  
E-mail: warshire@waroona.wa.gov.au

## **BIG SHED ADDITIONS AND ALTERATIONS**

### **Addendum No.2 Responses to Queries**

Please find enclosed Addendum No.2 dated 12th March 2025 for the above project. This Addendum is to be taken into account in preparation of tendered submissions.

Please acknowledge receipt of this addendum by signing the statement at the bottom of this page and returning it (by email) to the contact officer above prior to the closing date or by incorporating signed acknowledgement within your Tender Offer.

**Please note that failure to acknowledge receipt of this addendum may constitute cause for rejection of your submission.**

If your Tender Offer has been submitted prior to the receipt of this Addendum No. 1, acknowledgment and advice to that effect should urgently be made by email stating how the Tendered Offer may need to be changed to comply with the requirements of this Addendum. Such acknowledgment and advice must be received prior to the nominated closing time for receipt of Tendered Offers.

-----  
To: Contact Officer, Shire of Waroona.  
Email: warshire@waroona.wa.gov.au

I/We acknowledge receipt of Addendum No. 02 for 202425-04 Big Shed Additions and Alterations - Responses to Queries and have taken it into account in the preparation of our Tender Offer.

Signature: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Company Name: \_\_\_\_\_

Date: \_\_\_\_\_

# REQUEST FOR TENDER

## BIG SHED ADDITIONS AND ALTERATIONS - RESPONSES TO QUERIES

### Addendum No. 2

1. Finishes and equipment
2. CON-CLR1 will be C1 in the specifications 02274 Concrete Pavement
3. Appliances schedule

Item	Location	Manufacturer	Qty	Type	Colour/finish	Supplied by
Range Hood	Back Wall Counter	900 Artusi (Good Guys)	1	Electric		Contractor
Cooker	Back Wall Counter	Westinghouse 900 s/s WHG958SC	1	Gas	S/Steel	Contractor
Sink	Back Wall Counter	(SPECIFIED BY HYDRAULIC)	1			Contractor
Tapware	Back Wall Sink	(SPECIFIED BY HYDRAULIC)	1			Contractor
External BBQ	West Awning Area	Christie CC2, double with Icon series large cabinet	1	Gas		Contractor
Hot Water Unit	Back Wall	(SPECIFIED BY HYDRAULIC)	1	Gas		Contractor

4. Lining as per the schedule in the specifications

Item	Thickness/Type	Location	Support system	Remarks
James Hardie, Hardie Plank weatherboard	smooth 230mm	Store outer wall front	Steel stud framing	
James Hardie, Villaboard	9mm thick with flushed joints	Store inner walls	Steel stud framing	

5. Timber studs can be used in lieu of steel
6. Reclaimed timber in / on the big shed has not been specified based on available reclaimed timber from the Shire. Tenders should allow for the builder to supply reclaimed timber for the Big Shed. Reclaimed timber from the Shire to be used for the timber shelter
7. We have not noted replacing any timber purlins. The fascia boards are purlins and no allowance for replacement has been specified.
8. H3 timber battens to underside of decking will be acceptable in lieu of H4.
9. Stainless Benchtop 1.2mm thick 304 stainless steel is acceptable in lieu of 2mm 316 stainless steel. Site joints to be welded (seamless finish).
10. Finish to timber shelter to be painted, colours to match old scout hall building shown on the plans.